The following are the further conditions to which the contractor should bind himself :—

(*a*) That he shall prepare and remove the timber purchased by him before the end of March 1940.

(*b*) That he shall dress the logs on the spot. The District Forest Officer's decision regarding the overdressing of logs shall be final and the contractor shall pay such amount for wastage as may be fixed by the District Forest Officer.

(*c*) That only saws shall be used for cutting up the logs into required lengths and that only white wood, knots and flutes shall be removed while dressing the log and no unnecessary waste shall be caused.

(*d*) That he shall bind himself to pay in advance the value of the minimum quantity of timber to be fixed by the District Forest Officer and shall remove all marketable portions of a tree either in logs, pieces or poles.

(*e*) That he will not be eligible for any refund of advance revenue if the minimum quantity so fixed of each species is not removed, but any excess quantity removed shall be paid for at auction sale rate.

(*f*) That no timber prepared out of any tree shall be removed unless it is measured and stamped at the stump by the Range Officer or such other officer as the District Forest Officer may authorise and until it is duly paid for.

(*g*) That each consignment of timber shall be covered by a passport issued by the Range Officer or any other officer deputed by the District Forest Officer in this behalf.

(*h*) That he shall abide by the rules of the Department as regards the kindling of fires and shall hold himself responsible for any forest offences committed by his agents, employees or workmen.

(*i*) That if any tree which has been retained by the Department is felled, he shall pay a fine not exceeding Rs. 15 for each such tree.

(*j*) That no operations shall take place in the forest after sunset and before sunrise.

(*k*) That he shall not sublet the contract to anybody except with the written sanction of the District Forest Officer.

(*l*) That he shall have no right whatsoever over the timber paid for but left unremoved after the end of March 1940.

(*m*) That he shall maintain a register in the form prescribed by the District Forest Officer showing the number of trees felled and the outturn of timber from each of them and shall keep it open for the examination of Forest Officers above the grade of guards.

(*n*) That for any breach of any of the conditions of the contract by the contractor or his agents, the contract shall be void at the option of the District Forest Officer and that the latter may, after issuing to the contractor a notice of the cancellation of contract, enforce forfeiture of all or any part of the deposit and shall resell the right or work it departmentally at the risk of the contractor as in clause (2) *supra*. If the deposit or part thereof is so forfeited, it shall be immediately made good by the contractor.

Note.—Interest at 6½ per cent per annum will be levied on all arrears of amounts which are permitted be paid after the due date.

B. T. THIMMARAYAPPA,
District Forest Officer.

CHITALDRUG DISTRICT.

Abstract Notification dated 6th November 1939.

SALE OF KANKARI LIME STONE.

The attention of the public is invited to the detailed sale notification published in the *Mysore Gazette*, dated 16th November 1939, on page 2303, Part VI (place of sale being Sreerampur).

Abstract Notification dated 6th November 1939.

The attention of the public is hereby invited to the detailed notification, dated 6th November 1939, published on pages 2303-2304 of Part VI of the *Mysore Gazette*, dated 16th November 1939, calling for tenders for the purchase of the exclusive right of preparing charcoal out of Kamara trees marked for felling in the several Forests for the year 1939-40.

L. SRINIVASA MURTHI,
District Forest Officer.

ENGINEERING DEPARTMENT

BUILDINGS DIVISION, BANGALORE.

Abstract Notification.

The attention of the public is invited to the detailed notification published on page 2304 of Part VI of the *Mysore Gazette*, dated 16th November 1939, regarding the auction sale of sites in the proposed extension to the left of Bangalore-Hosur road or the road leading from the North gate of Lal-Bagh to the New Mental Hospital, Bangalore.

Notification dated 15th November 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 11th December 1939, for constructing single bed special ward in Victoria Hospital, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Buildings Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees four hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing single bed special wards in Victoria Hospital, Bangalore" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words, as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Detailed specifications for constructing single bed special wards for Victoria Hospital, Bangalore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation for foundations and removing the excavated earth to a distance of 50 yards and filling in basement with excavated earth duly watering and tamping in layers of 6″ thick (all soils)	C.yd.	0 3 0	154	
2	Burnt stone jelly concrete (jelly 1″ to 1½″) thick cubes in lime mortar with the proportion of 1 of lime, 2½ of sand and 4 of jelly for foundations laid in 6″ thick layers and well consolidated	C.ft.	0 3 6	1,668	
3	Burnt size stone in lime mortar of 1 of lime, 3 of sand in courses not less than 6″ high with bond stones at 6′ apart for foundation	,,	0 4 0	1,904	
4	Burnt size stone in lime mortar of 1 of lime, 3 of sand in courses not less than 6″ high with bond stones for every 6′ apart including quoins nicely dressed 2″ wide at corners for basement	,,	0 4 0	1,488	
5	Superstructure of burnt size stone in lime mortar, mortar to be of 1 of lime, 3 of sand laid in 6″ high courses with corners and quoins and jambs of doors and windows, etc., neatly dressed to 2″ wide, complete	,,	0 4 0	3,663	
5a	Burnt brick in lime mortar superstructure 9″ thick walls as partition with necessary bond stones for every 6th course with 1 of lime, 3 of sand	,,	0 4 0	333	
6	Burnt stone slabs 6″ thick set in lime mortar 1 of lime, 3 of sand with 2 lines dressing to the exposed surfaces including nice break joints complete for basement slabs for lintels above doors, windows and ventilators	S.ft.	0 4 6	1,381	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
7	Providing and fixing cut stone pillars with caps and bases (column to be of one foot dia. average 10' high as per design furnished during execution) ..	R.ft.	2 0 0	340	
8	Doors made of well seasoned Mysore Teakwood with frame of 3"×4", 1½" thick shutters ⅓ panelled at bottom and ⅔ glazed at top without bottom with ⅛" ground glass (glass of variety style will be specified during execution) with required type of ventilation complete with acme brass and copper oxidised fittings such as rim-door locks with handles, hinges, hooks, barrel bolts of suitable size will be specified including tarring wood work going into stone work with 2 coats of approved dulex Johnson & Nichelsons or any other kind of water proof varnish to be specified complete as per design furnished during construction size of doors 4'×9' ..	S.ft.	1 12 0	288	
8a	Small doors as per above specification without ventilators, complete	S.ft.	1 8 0	78	
9	Teakwood Mysore well seasoned teak 3"×4" frame with 1¼" thick glazed shutters in four halves and rebated both sides including ventilators type will be specified during execution with required specified glass, with required size of brass or copper oxidized hinges with necessary hookstoppers, etc., including 2 coats of Lac Factory green paint outside and dulex or Nichelson & Johnson varnish inside complete with tarring to the portion going in brick work. The design for the above will be furnished during execution, sizes with and without ventilators 4'×6', 4'×4' and 2'×6'.	Sqr.	1 12 0	301	
10	Ventilator, reinforced cement perforated ventilators, 1½" to 2" thick with 2" frame alround with necessary reinforcements as per design to be furnished during execution	S.ft.	0 8 0	63	
11	Roofing with R.C.C. 1 of cement, 2½ of sand and 4 of jelly, jelly of ½" cubes, 7½" to 8" thick to take a proper load of 1½ cwts. as per design which will be furnished during construction with necessary centrings, etc., including ceiling, plastering of 1 of lime and 3 of sand mortar with the approved design, roof finished both at bottom and top with chajja projection of 3'–0" projection	Sqr.	75 0 0	27·04	
12	Roofing of R.C.C. for verandah portion with 3' chajja projection with the specifications at an average 5" thick slabs	,,	55 0 0	20·54	
13	Plastering in lime mortar, ¾" thick, 1 part of lime 2 parts of sand, plastering to be done after racking out joints in the stone masonry finished and outside	,,	3 0 0	60·58	
14	Flooring with cement concrete, 1 part of cement, 2 parts of sand, 4 parts of jelly (well mixed) before laying the cement concrete to be of 1½" thick laid on a bed of 3" to 4" metal lime concrete of 1 part of lime, 3 parts of sand and 4 parts of jelly (jelly to be 1" to 1½" cubes) finished with topping of red cement plaster of ⅜" thick and lines cut to the required pattern (design will be furnished during construction) ..	,,	17 0 0	24·83	
15	Painting two coats of Government Lac Factory green paint	,,	4 0 0	13·40	
16	White and colour washing two coats as per P. W. D. specification	,,	0 4 0	60·58	
17	Cement pointing to basement alround with cut lines (1 : 2)	,,	3 0 0	42·47	

M. K. RAJAM IYENGAR,
Executive Engineer.